





**Eller Drive & McIntosh Road Intersection Improvement Feasibility Study** 

**Stakeholder Meeting 1:** 

**Existing Conditions and Improvement Concepts** 

February 2024





#### Agenda



Welcome and Opening

**Project Introduction** 

Field Observations and Assessment

**Existing Conditions Analysis** 

**Improvement Concepts** 

**Open Discussion** 

**Next Steps** 

















#### **Objectives:**

- Identify and evaluate five (5) alternatives that will improve traffic operations, mobility, and safety for all users of this intersection.
- Conduct an in-depth evaluation and recommend a preferred alternative to move forward for further development.









#### **Project Tasks**

- 1. Field Review/Observation
- 2. Existing and Future Conditions
- 3. Crash Data
- 4. Travel Demand Forecasting
- 5. Traffic Operational Analysis
- 6. Document Existing Conditions
- 7. Conceptual Design Alternatives

- 8. Construction Cost Estimating
- 9. Benefit-Cost Analysis (BCA)
- 10. Alternatives Evaluation
- 11. Recommendations
- 12. Meetings and Coordination
- 13. Stakeholder Presentations
- 14. Report Document



#### **April Field Observation**


- EB spillback
- NBLT trucks blocked



















































## **Existing Conditions Analysis**

#### **Existing Conditions – Crash History**



Crash Type	Frequency	Percent
Rear-End	21	28.38%
Angle	10	13.51%
<b>Backing</b>	8	10.81%
<mark>Sideswipe</mark>	24	32.43%
Turning	3	4.05%
Fixed Object	8	10.81%
<b>Total Crashes</b>	74	100%



2018-2022

40 NON - INJURY

8 INJURY OR FATAL

48 TOTAL

18 2019 5 2020 5 2021 7 2022

Wet Conditions

-W- Out of Control

**Existing Conditions – Microsimulation** 

#### **Existing Conditions – Intersection Operations**

#### Analysis completed for:

- Weekday morning, mid-day, afternoon
- Weekend morning, mid-day, afternoon

	Direction		Move	ment		Appr	oach	Intersection		
Intersection		Volume	Delay (sec)	Queue (ft)	LOS	Delay (sec)	LOS	Delay (sec)	LOS	
	EBL	29	83.5	81.1	F					
	EBT	640	79.1	392.2	E	62.6	E	51.27		
	EBR	205	8.0	164.6	Α					
	WBL	41	76.7	77.0	E				6	
Eller Drive at	WBT	242	11.0	128.1	В	16.0	В			
Mcintosh	WBR	189	9.3	165.2	Α					
Road	SBL	50	108.7	105.5	F				D	
	SBT	13	73.0	42.6	E	82.4	F			
	SBR	16	7.8	39.9	Α					
	NBL	229	60.7	339.7	E					
	NBT	48	65.3	190.2	E	63.2	E			
	NBR	38	75.8	85.9	Е					



## **Improvement Concepts**





#### **Approach to Improvements**




### 1. I-595 to McIntosh Rd Flyover + Eller Dr Gate Relocation



### 1. I-595 to McIntosh Rd Flyover + Eller Dr Gate Relocation



### 2. NB Truck Re-Routing








## 2. NB Truck Re-Routing



### 3. Diverged East/West + Eller Dr Gate Relocation





### 3. Diverged East/West + Eller Dr Gate Relocation



#### 4. Eller Dr Gate Elimination



### 4. Eller Dr Gate Elimination



## 5. No Build





#### Improvement Concepts for Further Evaluation

- 1. I-595 to McIntosh Rd Flyover + Eller Dr Gate Relocation
- 2. NB Truck Rerouting
- 3. Diverged East/West + Eller Dr Gate Relocation
- 4. Eller Dr Gate Relocation
- 5. No Build

# **Next Steps**





### **Next Steps**

- Conceptual Designs
- Flaws and Constraints
- Cost Estimate and BCA
- Alternative Evaluation

**Next Meeting: Early Summer 2024 – Flaws and Constraints** 

### **Schedule**

#	Task	2023					2024											
		AUG	SEP	ОСТ	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	
1	Field Review/Observation		•		<b>*</b>	•							: Oeliverable			andum/R	Report	
2	Existing and Future Conditions			•								<ul><li>✓ Draft/Partial Deliverable</li><li>✓ Weekly Progress Updates</li><li>✓ PEV &amp; FDOT Meeting</li></ul>						
3	Crash Data				<b>*</b>													
4	Travel Demand Forecasting						<b>*</b>					Stakeholder Meeting						
5	Traffic Operational Analysis						<b>*</b>				•							
6	Document Existing Conditions						<b>* *</b>							Nov	v in (	Conc	ept	
7	Conceptual Design Alternatives						•				<b>*</b>			Des				
8	Construction Cost Estimating										•			<b>D</b> 00	911			
9	Benefit-Cost Analysis (BCA)											•		Cor	nnla	ion:		
10	Alternatives Evaluation											•			nple	i .		
11	Recommendations												•	Oct	. 202	14		
12	Meetings and Coordination	•						<b>*</b>			<b>•</b>			<b>•</b>				
13	Stakeholder Presentations							<b>*</b>			•			<b>*</b>				
14	Report Document													•		<b>+</b>		
	Anticipated Meetings	•	9999	9999	9999	9999	9999	•••• •• ••	9999		•••• •••	9999	••••	••••• ••		9999		
		Kick Of	f					Ex+Cor	ncept		Fatal Fl	aws		AA+Re	comme		1	
													6	PORT		ED		

#### **Project Contact**

Dr. Natacha Yacinthe | PEV Project Manager | nyacinthe@broward.org

Luis Aguilar | PEV Task Lead | <u>luaguilar@broward.org</u>

Carlos Castro | FDOT Project Manager | carlos.castro@dot.state.fl.us

Peng Zhu | Consultant Project Manager | pzhu@transystems.com

